

Fox Body Cowl Vent Grille (83-93 all)

Time Needed: about 30 min

Tools Needed: Phillips screwdriver



Removal procedure:


Step 1: Lift up on the passenger side windshield wiper.



Step 2: Looking at the base of the wiper you will see a tab.




Step 2 continued: With your hands pull the tab out releasing the wiper.




Step 3: Pull the wiper off.



Step 4: With the screwdriver unscrew the 6 screws that hold the cowl to the car.



Step 5: Pic continued.



Step 6: After removing the 6 screws lift the cowl up, you will see a hose going to the sprayer.



Step 7: Pull the hose off the sprayer.



Step 8: With the cowl now free from the car, take a Philips screwdriver and remove the one screw holding the sprayer onto the cowl.



Installation procedure:

Step 1: Re install the sprayer to the new cowl with the 1 Phillips screw.

Step 2: Place the new cowl onto the car, plug the sprayer hose back onto the sprayer.

Step 3: Line up the cowl with the screw holes and tighten the 6 screws back into the cowl.



Step 4: Take the wiper and slide it back on.

Step 5: Lift up on the end of the wiper and push the retaining tab back in.



Step 6: Enjoy



Installation Instructions written by AmericanMuscle Customer Vance Clark 10.30.2014